



- 1 x Set of Powerlocks outgoing
- 3 x 125A 3PH Sockets
- 2 x 125A 240V Sockets
- 2 x 63A 240V Sockets
- 1 x 32A 240V Socket
- 1 x 16A 240V Socket
- 1 x 400A TP MCCB (with lock)
- 1 x Shunt Trip
- 1 x LED Variable Earth Leakage unit c/w CT

- 1 x Keyswitch, lamp, fuse
- 1 x Digital Multimeter
- 3 x 125A TP MCBs
- 2 x 125A SP MCBs
- 2 x 63A SP MCBs
- 1 x 32A SP MCB
- 1 x 16A SP MCB
- 1 x Set Incoming Neons